SHIMOGA DIVISION.

Dated 27th November 1928.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 17th December 1928, for restoring Bommarsikoppa Manigatta Tank, Registered No. 202—981 of Sorab Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1929.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga, between the hours of 11 A.M. to 5 P.M. on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of Rs. 500 in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for restoring Bommarsikoppa Manigatta Tank Registered No. 202—981 of Sorab Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer of Mysore, Bangalore who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract quantity of estimate for restoring Bommarsikoppa Manigattekere Major Tank, Registered No. 202 and 981 of Sorab Taluk.

No.	Items of work	Per	Quantity
	Bund.		
1	Jungle clearing and removing Ant hills	Lump	sum
2	Cutting grips for joining old and new earthwork ...	S.yd.	12,100
3	Earthwork to bund including Excavating, carrying, watering, consolidating, etc., complete.	C.yd.	7,049
4	Earthwork excavation for foundation of revetment, and utilizing the same to bund with consolidation.	,,	766
5	Revetment for front slope including jelly packing with a lead of 2½ miles for stones.	,,	652
6	Gravel backing 6" thick behind revetment with a lead of ½ mile for gravel.	,,	217
7	Turfing	Sqr.	698
8	Grade stones with bed slabs including figuring and fixing, etc., complete.	Each	38
9	Index stones	,,	38
10	Registered No. and date stone with figuring and fixing complete.	,,	1
11	B. M. stones with figuring and fixing complete ...	,,	2
12	Gauge stone do do ...	,,	1

No.	Items of work	Per	Quantity
	Sluice No. 1		
1	Earthwork excavating and filling in with consolidation after construction.	C.yd.	7
2	Stone jelly concrete in Surki mortar	C.ft.	88
3	Burnt brick in Surki mortar	,,	55
3a	Burnt stone in do	,,	55
4	Burnt stone slabs 4½" thick dressed and fixed complete ...	S.ft.	25
5	Plastering with Surki mortar	Sqr.	0·50
6	Cement concrete 3" thick with rendering on top of front and rear headwalls.	Lump	sum
7	C. I. pipes 10" dia including railway freight, carting to to work spot and fixing with cement joints, etc., complete.	R.ft.	24
8	Wooden plug	Each	1
	Sluice No. 2.		
1	Earthwork excavation and filling in with consolidation after contruction.	C.yd.	40
2	Stone jelly concrete in Surki mortar	C.ft.	164
3	Burnt brick in Surki mortar	,,	196
3a	Bunt stone in do	,,	196
4	Brunt stone slabs 4½" thick dressed and fixed ...	S.ft.	60
5	Surki mortar plastering	Sqr.	1
6	Cutting orifices in slabes	Each	3
7	C. I. pipes 7" dia including railway freight carting to the work spots and fixing with cement points, etc., complete.	R.ft.	24
8	Teakwood plug with iron rod, etc., complete ...	Each	1
	Sluice No. 3.		
1	Earthwork excavation and filling in with consolidation after construction.	C.yd.	29
2	Stone jelly concrete in Surki mortar	C.ft.	118
3	Burnt brick in Surki mortar	,,	104
3a	Burnt stone in Surki mortar	,,	104
4	Burnt stone slabs 4½" thick dressed and fixed, etc., complete.	S.ft.	47
5	Surki mortar plastering	Sqr.	1
6	Cutting orifices in slabs	Each	3
7	Cast iron pipes 7" dia including railway freight carting fixing with cement joints, etc., complete.	R.ft	24
8	Teakwood plug with iron rod, etc., complete ...	Each	1
	Sluice No. 4.		
1	Earthwork excavation and filling in with consolidation after construction.	C.yd.	14
2	Stone jelly concrete in surki mortar	C.ft.	88
3	Burnt brick in surki mortar	,,	54
3a	Burnt stone in surki mortar	,,	54
4	Burnt stone slabs 4½" thick dressed and fixed, etc., complete.	S.ft.	25
5	Plastering with surki mortar	Sqr.	1
6	Cement concrete 3" thick with rendering on front and rear headwall.	Lump	sum
7	Cast iron pipe 6" dia including railway freight carting to work spot and fixing with cement joints, etc., complete.	R.ft.	24
8	Wooden plug	Each	1
	Waste Weir Natural.		
1	Clearing obstruction in the draft channel of lift waste weir...	Lump	sum
2	Revetment to both the ends of bund	Lump	sum